

PERFORMANCE RESULTS

O'Reilly Oakstown Environmental Ltd.

Oakstown, Trim
Co. Meath
Ireland

EN 12566-1

Part 1: Prefabricated septic tanks
Results corresponding to the Irish National Annex IS EN 12566-1

Oakstown Septic Tank

| | |
|------------------------------------|----------------------------|
| Material | concrete |
| Hydraulic efficiency (Annex B) | 99.68 % |
| Nominal capacity (usable volume) | 3 m ³ (3,409 l) |
| Watertightness (water test) | pass |
| Structural behaviour (calculation) | pass (also wet conditions) |
| Durability | pass |

Performance tested by:

PIA – Prüfinstitut für Abwassertechnik GmbH

(PIA GmbH)

Hergenrather Weg 30

D-52074 Aachen

Certified according to
ISO 9001:2008



Notified Body number: 1739



This document replaces neither the declaration
of conformity nor the CE marking.

Prüfinstitut für Abwassertechnik GmbH

geprüft - tested - testé

Elmar Lancé

October 2012